

# Contractor 300kg Lift Model 2118



#### SPECIFICATIONS

Max Lift	300kg
Raised Maximum Height	5m
Max Height - Forks Reversed	5.6m
Singleman Loading Wheels	yes
Finish	Galvanised
Mast Winch	yes
Weight	161.8kg

The Kerrick range of material lifts delivers the perfect platform for the installation and construction industries. Built to our high standards they have all the safety features needed to ensure a productive and safe working environment, this series of lifts offers the versatility that the industry needs. Popular in the hire industry, building and construction, industrial air conditioning industries. These material handling lifts have been designed to fit through standard doorways (820mm wide).

## Part No.: SUM2118 Usage rating:

### FEATURES

- Cable Stay Brake
- Unique Mast Hold-Down
- Reversible Forks
- Lockable 5" Casters
- Loading Bar
- Roller Wheels
- Inside-Mast Cable Feed
- 10" Rough Terrain Wheels
- Fast Action Stabilizer Legs

### EXTRAS

- Fork extensions
- Boom carriage

1300 KERRICK

- Pipe craddle
- **1 YEAR COMMERCIAL WARRANTY**

# **Kerrick Branches**

New South Wales	98-104 Carnarvon Street Silverwater New South Wales 2128	(02)97379797
Queensland	126 Robinson Rd Geebung Queensland 4034	(07)38652551
South Australia	31 West Thebarton Rd Thebarton South Australia 5031	(08)83408060
Victoria	41 Pacific Dr Keysborough Victoria 3173	(03)87691500
Western Australia	23 Belmont Ave Belmont Western Australia 6104	(08)92779651

